



## Aluminum Paint Line Upgrade

### ***The Application***

An aluminum manufacturer of building and construction industry products had experienced strip-tracking difficulties resulting in line “crashes” and poor strip quality on its 22-year old paint line. A crash not only took the line out of production, but also resulted in a large amount of scrap material. Recovering from a crash is a time consuming operation. Outdated equipment made it difficult to make process improvements. An engineering study identified the need for improved tension control in order for the line to resume running at its original design speed.

The overall project consisted of several smaller projects that were a combination of:

- Electrical controls upgrade
- Mechanical modifications
- Integration of purchased subsystems
- Installation planning and execution

Implementation of these improvements had to be made with minimal disruption to the production schedule.



### ***The PCT Solution***

PCT was asked to replace the paint line’s existing bridle roll drives, motors and gearboxes in order for it to operate with improved tension control.

In addition, PCT provided:

- Programming of a new controller to integrate the new drives into the existing line control.
- Reassignment of the master bridle function to improve tension isolation between line sections.
- Mechanical and electrical design and installation of four load cell systems for tension feedback and monitoring.

**Metals**



- Mechanical and electrical installation and commissioning of two ultrasonic coil diameter sensors located at the payoffs and control units for sensors located at the payoff and control units for the rage brake and unwind tension control.
- A new center guide system for the rewind mandrel to improve wrapping accuracy and to accommodate increased line speeds.
- Specification and installation of a new hydraulic unit to meet performance requirements of the new center guide system.



- As a result of past relationships developed during cooperative projects, PCT was able to partner with Rockwell Automation for the paint line upgrade. PCT saw partnering as a way to reduce development time, minimize risk and provide comprehensive commissioning support. Rockwell's Drive Systems group provided a key portion of the tension control and the GTS group was involved in startup of the project.
- PCT provided the engineering, design, hardware and documentation necessary to install new DC drives, DC motors and gear reducers. The new drives were installed in the existing drive control cabinets in order to keep project costs down. New motors and gear reducers were supplied with the necessary coupling and mounting bases allowing for easier installation in the existing bridle locations. PCT also provided programming, tuning and commissioning of the new drives and motors.
- The aluminum manufacturer's plant manager is pleased with the process improvements that PCT's engineering team provided within a short and demanding project schedule. Improved tension control resulting in the reduction of strip-tracking difficulties has improved product quality, and has allowed the paint line to meet and exceed production expectations.

**PCT**  
 Engineered Systems, LLC  
*The Solutions Team*

5433 Tremont Ave.  
 Davenport, IA 52807  
 563.391.8011  
 FAX 563.391.8432  
[www.teampct.com](http://www.teampct.com)

